



Racing and Competing Rules

02 -03- 2022

Index

Pages 1 & 2

Section A - Offshore Circuit Racing – Classes and Race Boat Requirements

1. Definitions	Page 3
2. Classes	Page 3
3. Boat Registration	Page 4
4. Licenses	Page 4
5. Age Regulations	Page 5
6. Control of Boat	Page 5
7. Novice Crew	Page 5
8. Race Entries	Page 5
9. Race Boat Numbers	Pages 5 & 6
10. Race Boat Equipment	Pages 6, 7, 8, 9 & 10,
11. Modifications to Engines	Page 10
12. Scrutineering	Page 11

Section B - General Rules and Definitions

1. Eligibility	Page 11
2. Pre-Race Declaration	Pages 11 & 12
3. Competitors Responsibility	Page 12
4. Points	Pages 12 & 13
5. Alcohol & Drug Testing	Page 13
6. Valid Starters	Page 13
7. Flags	Page 14
8. Posting of results	Page 15
9. Penalties and Warnings	Page 15
10. Protests	Pages 15 & 16



Index – Continued

Section C – Launching and Start Procedures

- | | |
|--|-------------------|
| 1. Launching | Page 16 |
| 2. Transit to and Waiting in the Muster Area | Page 16 |
| 3. Start Procedure | Pages 16, 17 & 18 |

Section D – Racing Rules

- | | |
|--------------------------|---------------|
| 1. General | Page 18 |
| 2. Wet Driver / Crew | Page 18 |
| 3. Accident Aid | Page 19 |
| 4. Yellow Flag | Page 19 |
| 5. Red Flag | Page 19 |
| 6. Overtaking | Pages 19 & 20 |
| 7. Multiclass Racing | Page 20 |
| 8. Turn Marks | Page 20 |
| 9. Finishing a Race | Page 20 & 21 |
| 10. Race Curtailment | Page 21 |
| 11. Retirement Procedure | Page 21 |
| 12. Injured Crew | Page 21 |

Section E – Jet Ski Appendices

- | | |
|---|-----------|
| Appendix 1 -_Modifications permitted in 300 hp and 200 hp stock | – Page 22 |
| Appendix 2 – Jet Ski Numbers | Page 23 |
| Appendix 3 – Jet Ski Helmets | Page 23 |
| Appendix 4 – Jet Ski Starting Procedure | Page 24 |

Please Note:- All Rule Changes / amendments for this year are shown in

Red

Small Grammatical changes are not highlighted

Terminology.

In these rules the word “shall or “must” means mandatory “should” or “may” means recommended

“Driver” refers to “Boat Driver” and “Jet Ski Rider”

“Boat” refers to ALL “Race Craft”



IMPORTANT: - Safety is Paramount and any competitor acting in a dangerous or unsafe manner will be disqualified.



Section A - Offshore Circuit Racing – Classes and Race Boat Requirements

1. Classes & Engines

The OCR Series shall be sub-divided into four single engine classes / formula. To identify which class / formula a boat is in, the class calculator on the OCRDA web site is to be used. Generally, this will be according to the engine manufacturer's specification as detailed below:

OCR Classes Cubic Capacity / hp

Formula Sport - N/A – Single outboard unless specifically agreed by the OCRDA Committee

Formula 1 Up to 2750cc - Max 199hp

Formula 2 Up to 2200cc - Max 149hp (including experimental single seater – see below)

Experimental class for 2022 using a central single seat configuration are to comply with the following: -

- i. Any boat which fits within the F3 category may be run in the F2 Class as a single seater
- ii. When using the class calculator the 'MODIFIED' box should be ticked
- iii. Single seater boats must have a fluorescent pink 'X' affixed to the rear of the engine cowling which shall be as big as possible using all the space available.
- iv. All engines must be stock engines as per the requirements for F3 with no modifications.
Note: - the above will be kept under review throughout the season and amended if required.

Formula 3 Up to 1500cc - Max 100hp

Jet Ski Classes

J1 - 300+ 300hp modified

J2 - 300 300hp Stock and 200hp modified

J3 - 200 Up to 200hp Stock

Jet Ski's please see Section E Appendix 1 at the end of this document for permitted modifications.

2. Boats / Hull

- a) With no specific boat design criteria, competitors should ensure that their engines fall within the boat hull manufactures specification and should seek confirmation from OCRDA as to the eligibility of a boat and its engine prior to entry (see registration logbook below).
- b) Boats requiring weight to meet formula requirements may only add a maximum of 10% of the boats original weight. This weight must be permanently bolted or fibreglassed inside the boat evenly divided between the transom and crew area. No fixed weight will be allowed forward of the front 1/3 of the boat.
- c) Any loose ballast / trimming weight can be positioned anywhere within the boat. Trimming weight will be removed when a boat is weighed for its classification.
- d) OCRDA reserves the right to refuse entry to any boat and /or crew. If requested reasons for refusal will be submitted in writing.
- e) Anyone who feels their boat has been put in the wrong class then they should send their reasons by e-mail to admin@ocrda.com this will normally be responded to within 14 days from receipt.

IMPORTANT: - Safety is Paramount and any competitor acting in a dangerous or unsafe manner will be disqualified.

3. Boat Registration

- a) All boats that are intending to be raced must be registered with OCRDA. Registration will relate to both the owner and the boat.
- b) The cost of boat registration will include one non-refundable race entry.
- c) Once registration has been accepted OCRDA will issue a registration logbook which must be presented at race control at each event along with their race licence.
- d) **Class stickers in Oracle 7510 Vinyl are to be fitted to the bow of the boat of each of the following OCR classes (For Jet Ski's please see Appendix 2) as follows: -**
F Sport – Not Required
F1 Yellow - 029
F2 Pink - 046
F3 Red - 037
They should be fitted on the top and both sides and extend 500mm back from the bow with the appropriate class shown in 100mm black (If you are not sure of the precise position on the class stickers please ask).
- e) Should any boat be damaged, the Scrutineer will advise the Race Secretary to record details of any such damage in the boat's logbook
- f) Any damage or injury sustained at an OCRDA event may be recorded on the relevant incident form to be used as part of a separate record of incidents at an event.

4. Licences

To enter the OCR series all competitors must be a full member of OCRDA and be in possession of a valid OCRDA powerboat racing licence which can be obtained as follows: -

- a) Requested from the OCRDA Secretary admin@ocrda.com or **downloaded from the web site.**
Please ensure you complete all sections.
- b) For the 18 to 60 age groups the application form shall be accompanied by an OCRDA self-declaration medical form which should be accurately filled in and if necessary, obtain the relevant approval from a qualified doctor. Applicants outside of these age groups will require a full medical.
- c) If appropriate the applicant must carry out the relevant powerboat training (see training section) before the licence can be issued.
- d) Return the racing licence application form to OCRDA together with the completed medical form, evidence of training (if appropriate) and the fee as stated on the form.
- e) OCRDA licences will be valid only for the calendar year in which it was issued. At the discretion of OCRDA a discount may be applied for licences issued mid-season.
- f) Valid licences from any other national authority will also be considered although a fee may apply.

It is Highly RECOMMENDED that all competitors take out sufficient personal accident insurance to meet their individual needs. This requirement will also be shown on each licence application and a declaration that it is still in existence by a competitor signing on at an event.

5. Age Regulations

- a) In all OCR classes the minimum age for a navigator is 16 and driver is 18 years of age
- b) In Jet Ski's the minimum age is 16 Years of age
- c) All age regulations apply on the first day of an event.
- d) All Competitors under the age of 18 must provide proof of age
- e) All competitors under the age of 18 must be accompanied at the event by a Parent/Guardian
- f) All competitors under the age of 18 on the date of the race will be required to submit written consent of their parent or guardian to their participation in the race and confirmation of their acceptance of the rules governing the race and the risks involved.
- g) Jet Ski Riders under the age of 18 may only enter J3 class.
- h) Jet Ski Riders under 18's will be required to wear hi viz race vest

6. Control of Boat

- a) Only valid licence holders are permitted to control or be in the boat whilst racing.
- b) Only the Driver signed onto the event is allowed to drive the boat during a race. Any change over of Driver / Navigator or change of any of the boats crew must be authorised by Race Control / Race Manager before the change takes place. Any request for any changes is to be supported with the reasons why.
- c) Boats are ONLY allowed out on the water when signed on at the times designated in race instructions or with the prior agreement of the Race Manager or Safety Control Officer. Any boat on the water prior to signing on must obey all local bylaws and liaise with the local harbour authority. Non-conformance may result in disqualification from the event and / or fined by the authorities.

7. Novice Crew

- a) Any team with a crew member competing in his or her first 3 events (Classified as a Novice) **MAY** be required to display identification that they are a novice. Details of this will be given in advance if required. Novices entering in a **Formula sport or Formula 1** boat will only be permitted at the discretion of the race organisers / OCRDA committee.
- b) These teams may need to be positioned furthest from the start boat during their first four races, this will be detailed in race instructions or at the drivers briefing.
- c) Novice Drivers and Co-drivers will be under periodic review to monitor their performance and where necessary may be required to undertake additional training

8. Race Entries

- a) All entries must be made via the official entry form and all accompanying terms and conditions complied with.
- b) Entry of any team into any race of the championship is fully at the sole discretion of OCRDA and the organisers reserve the right to refuse entry.
- c) OCRDA reserve the right to refuse entry to any boat and /or crew. If requested reasons for refusal will be submitted in writing.

9. Race Boat Numbers – For further information on jet Ski Numbers please see Appendix 2.

- a) Race boat numbers will be issued by OCRDA to the driver on a first come first served basis and cannot be changed during the season.
- b) Once issued you will be entitled to retain that number as long as the boat registration is renewed annually by the 31st of December and that you continue to be a fully paid up OCRDA member.

- c) All race boat / Jet numbers will be recorded in your OCRDA Registration Logbook. All numbers shall be black on a white background (or yellow for white boats). There should be at least 25mm of background colour surrounding the race boat number. Numbers must be on both sides of the boat and optionally on the foredeck. Numbers on the foredeck shall read correctly when viewed from the transom
- d) **All** Numbers shall be bold, clearly visible (no italics), with a minimum Height of 300mm. In the case of small boats these dimensions may be decreased but the maximum use of available space is to be used.
- e) Boat / Ski numbers shall also be displayed on both sides of the trailer hitch.

10. Race Boat and Equipment

a) Cranage and Recovery

- i. If the Boat is to be craned at any event it is recommended that it be fitted with a minimum of three lifting eyes suitably engineered to withstand lifting the boat fully equipped and fuelled with an adequate safety margin.
- ii. If slings are used, then ideally, they should be used with spreader bars.
- iii. Boats are lifted at the owner's responsibility and it is his / her responsibility to ensure the correct positioning of all strops and that they are certified, adequate and within the SWL for the boat's weight including any equipment when it is being lifted.
- iv. No persons are allowed on board any boat whilst being craned / lifted
- v. Boats being craned / lifted must not pass over the head of any person or another boat.
- vi. Everyone in the craning area must always wear either a hard hat or a racing helmet.

b) Trailers

- i. To aid identification Boat race numbers must be clearly displayed on both sides of the trailer hitch.
- ii. All trailers (including jockey wheel, winches, winch straps, winch handles and brakes) should be in a good and roadworthy state of repair. Wheel blocks should always be available to be used if required.
- iii. Trailers shall have no smoking signs on either side of the winch post.
- iv. A portable in date fire extinguisher is to be mounted on the front part of the trailer

c) Towing Cleats and Eyes

Towing cleats and eyes shall be of adequate construction and strength for the boat to be towed when waterlogged and shall be securely fixed to the main hull structure and not merely to the deck.

d) Decks

Decks must be able to bear the weight of a 100 Kg person standing at any point.

e) Windshields and Windscreens

- i. Must be well secured.
- ii. Must be of non-splintering material. The use of glass for windscreens is forbidden except where they are made from toughened glass.
- iii. Must be masked by rubber or plastic on any bare edges.
- iv. Must not be so designed that it would restrict the driver from being ejected.
- v. All sharp edges must be adequately protected or removed.

f) Buoyancy

It is a mandatory requirement that suitable buoyancy be installed and properly secured in the bow of the boat.

g) Steering and Controls

- i. All steering system components, control cables, linkages, quadrants and any fitting within the steering system must be in good condition, secure and fit for purpose.
- ii. Hydraulic steering must be fully operative, hoses and unions must be free of leaks and adequately protected.
- iii. Single push pull steering is not permitted except for Jet Ski's.
- iv. It is highly recommended that Hydraulic steering is used in all classes.
- v. Formula 2 boats and above are to have a matched 1500psi Steering System. 1000psi high-capacity side mount systems may be acceptable subject to OCRDA approval.
- vi. All control cables shall be in good working order, securely fastened and any loose ends taped over.

h) Engine Cut-Off

- i. Engine cut-off device ("kill switch") ~~for connection to the driver and Navigator is mandatory.~~
- ii. ~~With the exception of Jet Ski's~~ an emergency override system or additional kill cord is to ~~be secured inside the boat with easy access~~ to allow the engine to be restarted if the driver is not in the boat. Co Pilots / navigators will be required to demonstrate their ability to restart the engine and drive the boat if required.
- iii. Kill cords must not exceed 120cm between driver and the connection to the boat.
- iv. The emergency cut-off device must be positioned so that when it operates, the connection cord and cap or clip will not catch or foul.
- v. Kill Switches are to be connected to the driver at ALL times when the engine is running.
- vi. Boats with a tandem set up are required to be fitted with a kill switch for both the Driver and Co-pilot / Navigator ~~along with an audio/visual alarm which will activate in the event of the Co-pilot / Navigator being ejected from the boat.~~

i) Throttle Control and Gears.

- i. Throttles must be properly connected, work freely and must be in a position where it cannot be fouled. It must quickly return the engine to idling speed when released and have a secondary means of return in the event of failure
- ii. All craft must be able to be manoeuvred ahead and astern under power and have neutral capability with controls at the driver's position.
- iii. ~~With the exception of Jet Ski's~~ Hand throttles are not permitted.

j) Seats

- i. All boats must have a min of two seats of adequate strength and support and must be secure and unmoveable.
- ii. It is **HIGHLY RECOMMENDED** that seat backs are of sufficient height to support the back of the head.
- iii. An infill behind the front seats is permitted but in the case of tandem seating the infill must start behind the navigator / co-driver's seat. Infills must be at least 40mm below the top of the seat backs and must be securely fitted. Should an infill be removed or not fitted all pins and brackets must be removed from the hull/deck.
- iv. Where practical seat height should be such that each crew members shoulder should be level with the adjacent top side of the boat.

k) Fuel and Fuel Tanks

- i. There is to be no refuelling between races on the same day. Boats should carry enough fuel to complete the days racing allowing for reasonable delays and restarts.
- ii. Only commercially available fuel with the same characteristics as that available to the public is to be used.

- iii. All tanks shall be secure in all directions undamaged and not leak.
- iv. **With the exception of Jet Ski's** there shall be a clearly marked and easily accessible means of shutting the fuel supply off from the tank(s)).
- v. Permanent metal tanks shall be earthed.
- vi. Fuel lines shall be leak and chafe resistant and run in a manner to avoid damage.
- vii. **All teams are advised to have their own fuel / oil spill kit**

l) Engine Mounting & Hazards

- i. Mounting brackets and clamps must be secure and in a satisfactory condition and attached to the transom with at least four bolts each secured with locking nuts and must be to the satisfaction of the scrutineer.
- ii. The engine must be free of dangerous corrosion, oil or fuel leaks or excessive heating likely to be a fire hazard or a danger to any adjacent structure within the boat.

m) Batteries

- i. A clearly marked battery isolation switch in the positive or negative supply line shall be fitted in an accessible position within the boat - **Excluding Jet Ski's**
- ii. All batteries shall be mounted upon a secure and solid platform and secured with fittings sufficiently strong to withstand any anticipated shock or inertia encountered during a race.
- iii. Batteries shall be free of corrosive leaks and well maintained to the satisfaction of the scrutineer.

n) Propeller Security

- i. It is the responsibility of the competitor to ensure that the propeller or propellers are sound, particularly at the blade roots and are securely locked by the propeller nut(s).
- ii. When the boat is not in the water, the propeller shall be fitted with a suitable guard which is sufficient to prevent injury in the event of any physical contact by a person.

o) Engine Well – Outboards

All holes cut into the bulkheads of the engine mounting structure for the purpose of passing control cables etc, must be watertight, as high as possible and above the level of the lowest point of the transom cut-out.

p) Bilge Pumps and Bailing

- i. There shall be at least one electric bilge pump fitted to the boat. The number and capacity of pumps installed shall be appropriate to the size of the boat.
- ii. All bilge pumps shall be in proper working order and secured to the boat.
- iii. it is MANDATORY that in addition to the electric bilge pump a secondary means of bailing is available within the boat (e.g. Bailing bucket or manual bilge pump) **Excludes Jet Ski's**

q) Helmets – OCR Only - for Jet Ski's Please see appendix 3

- i. Full face protective helmets of the correct size must be worn by all persons on board at any time when the boat is on the plane, during the journey to and from the race, during racing and practice or testing. Helmets may be removed during the race if the boat is adrift or at anchor with engines stopped or idling.
- ii. It is mandatory to wear the **appropriate size of helmet and that it fits correctly. Helmets shall** be made to a minimum standard to include UN ECE22-05 or Snell M2000, or M2005 or Snell SA2000 or SA2005. All Helmets must have temple protection.
- iii. **Front Flip up Helmets are not permitted**
- iv. The efficiency and condition of a helmet is the sole responsibility of the wearer who should satisfy themselves that as well as meeting the above standards that it is 'fit for purpose'

- v. When a helmet is first produced for scrutineering the wearer must prove compliance with the above standards; this may be by means of product literature.
- vi. Chin straps must be in good condition and operate correctly.
- vii. Helmets must be devoid of dents or splits.
- viii. Helmet visors must be in good condition and devoid of cracks and easily detachable.
- ix. It is mandatory to have an intercom system, between driver and navigator, installed **and for it to be fully operational.**
- x. Helmets shall be in predominantly bright orange, yellow or green and shall have no stickers other than a reference to the safety standard of that helmet and the boat number being raced which should be clearly visible on the top of the helmet. It is also recommended that the wearers name is shown on the helmet at chin level.

s) Lifejackets

- i. Lifejackets must be **worn at ALL times** by any person on board whilst the boat is on the water.
- ii. The efficiency of any jacket is the responsibility of the wearer, but the conditions specified in this section must be complied with.
- iii. All jackets must have an inherent buoyancy suitable for the wearer and shall be fitted with a collar.
- iv. Lacing ties and/or straps shall be adequate and in good condition. There must be lifting straps at the front or on the shoulders and have a lifting eye or strap attached to the main harness.
- v. Zips are not permitted as the sole means of fastening a jacket. Where zips are used as an ancillary means of closure must be provided and both should be in working order.
- vi. Tears or rips or bad repairs through which buoyancy material may leak out are not permitted
- vii. Jackets must be at least 70% orange, Red or yellow or have orange, red or yellow panels.
- viii. Jackets must not be able to ride up over the wearer's head and must be secure to the body.
- ix. The disposition of the solid buoyancy must be such as to ensure that an unconscious person will float face up in the water.
- x. The jacket must have impact protection material covering the back. Examples of the type of jacket that comply with the above are the Hutch Wilco, Grabner, Formula, Aqua Stop. Please contact OCRDA for additional information if you are unsure of the type of product that is acceptable.

t) Towing Lines & Mooring Fenders

- i. A suitable tow rope with a spring loaded snap hook on one end is to be safely secured within the boat at all times whilst racing.
- ii. All towing lines and the towing point must be of adequate construction and strength for the boat to be towed when waterlogged.
- iii. Towing lines should be no longer than the length of the boat to prevent it fouling the prop should it become detached
- iv. All boats shall carry adequate and suitable fenders and mooring lines for use when moored alongside another boat.

u) Rope Cutter

All crew members must carry a suitable rope cutter (not a belt cutter) on their person. **KNIVES ARE NOT PERMITTED** - Excludes Jet Ski's.

v) Retirement Flag – Excludes Jet Ski's

- i. All boats shall carry an orange rectangular flag of a minimum size of 0.60m x 0.40m as a means of announcing retirement from a race. Retirement flags are to be kept aloft at all times once retired if practical so as to distinguish retired craft from those still racing. The Orange Flag should be waved vigorously if urgent assistance is required.
- ii. Once a boat has retired it cannot, under any circumstances, continue or re-start racing.

w) Advertising

- i. Sponsor decals and application instructions may be issued by the organising body. It is the responsibility of each driver to ensure these are placed on their boat as directed.
- ii. No owner or crew can be compelled to carry any conflicting advertising whatsoever on their person, clothes or upon the boat that is being raced and their refusal to do so cannot in anyway be an obstacle to their participation in any race.
- iii. Political publicity or immoral advertisements are not allowed.
- iv. No advertising is to contain any inappropriate or offensive words or images.

x) National Flag

All boats MUST display their national flag (minimum 350mm x 200mm) throughout the race along with OCRDA, BPBA and UIM Stickers.

y) Protective Clothing

Protective clothing in the form of race overalls and footwear which covers all limbs must be worn at all times whilst on the water in the boat.

z) Scrutineering

- i. It shall be the competitor's responsibility to offer for scrutiny a boat that does not have any structural or mechanical defects.
- ii. All safety equipment required must be carried on board and fixed/stored for the Scrutineer to see to their satisfaction.

11. Modifications to Engines

Any change or modification that is not allowed for in these rules will result in disqualification from the race. Should you wish to make a modification not listed below and to avoid disqualification please request clarification from the committee via the club secretary.

- i. It is permitted to modify the engine cowling.
- ii. It is recommended the engine rubber mounts be substituted with a solid alternative.
- iii. Blueprinting of the powerhead to the manufacturer's tolerances is permitted.
- iv. Transom brackets may be reinforced.
- v. The fuel connector in the lower cover may be removed and the fuel hose from the fuel tank connected directly to the fuel pump.
- vi. Modified production engines will be assumed as race engines and classed accordingly.
- vii. 15 inch mid and / or low water pick-ups are permitted in F Sport only.

(Definition of modified - Power enhancing modifications to the powerhead, Sandwich /adapter plates, exhaust tuners, ECU and electronic components. If any of these components have been modified from their original factory settings, configuration or tolerances 'Modified' must be declared on logbook application. Saddles, trim assembly and Engine Mounts are permitted modifications. If any openings have been cut or drilled in mid-section 'exhaust relief' must be selected in the logbook.)

12. Scrutineering

a) Scrutineers Inspections.

- i. Scrutineering does not constitute a condition survey of the boat and should not be taken that the boat is safe to race.
- ii. Scrutineers will use the current OCRDA Scrutineering Sheets. The scrutineering sheet may not necessarily cover every item that a scrutineer may wish / need to check on a particular boat nor does every item necessarily refer to every class of boat. A scrutineer will reject a boat if it does not comply with the rules and / or the requirements of the organiser and any non-compliance referred to the race committee. Any decision will be taken as quickly as possible to allow where appropriate changes to be made before the start of a race.
- iii. Any boat failing its initial scrutineering will be re-examined should time permit.
- iv. Boat compliance checks may take place at any time during an event and penalties applied as deemed suitable by the race committee.

b) Damaged Boats – Logbooks

If during an event a boat is damaged so as to be deemed unfit to race, the Race Scrutineer will complete the relevant part of the logbook and give a copy to the competitor. The boats logbook will be withdrawn by OCRDA and only be reissued after the competitor provides proof from a competent person that the boat has been examined after repairs have been made and deemed fit to race. Ultimately it is the competitor's responsibility to ensure that a boat is fit to race. In addition, any recommendations made to a competitor about the condition of a boat will be noted on the logbook.

Section B - General Rules and Definitions

1. Eligibility

It is the Race Committee's duty to decide upon competitor's eligibility and as to whether boats and engines conform to the rules. If a Race Committee decides to check an engine to verify its eligibility, the cost shall be borne by the competitor if the engine fails the eligibility check, otherwise the cost will be borne by the race organiser.

2. Pre- Race Declaration, Signing On, Signing Off and Race Briefing

- a) All drivers and crew members must be fully paid-up members of OCRDA and shall sign the indemnity waiver form.
- b) Any team who are not in race administration with their relevant event registration paperwork at least 30 minutes prior to briefing may not have their paperwork processed and therefore will not be able to race.
- c) All competitors are required to sign on prior to the start of the event to signify their attendance. Failure to sign on without a lead officials' consent will result in a penalty or disqualification.
- d) All Competitors remain signed on to the event at all times race control is open as detailed in race instructions. Competitors will automatically be signed off from the event once race control closes after the last race at an event.
- e) **Signing off (fit and well)**
At the end of each day's racing once their boat has been recovered all competitors are required to sign off confirming that they are fit and well. Once the last person signs off Medical Support will be stood down.
- f) Any protest with regards to eligibility must be made to the Race Manager prior to the start of each briefing.

g) Non-attendance at the start of the briefing without the consent of a race official may result in disqualification or other penalties being applied.

h) Identity Tags

Racing crew members will be issued with a waterproof temporary identification tag when they first sign on and this must always be worn on the right wrist (unless specifically agreed by the race officials) for the duration of the event. It can only be removed once signed off from their last race.

3. Competitors Responsibility

a) The competitors accept responsibility for every eventuality that may occur as a result of entering a race. It is the crews sole and ultimate responsibility to decide whether to start or continue in a race once they have passed scrutineering.

b) It is forbidden to start the motor with the propeller rotating in the air.

c) Smoking of any type is strictly prohibited in the boat, pits, fuelling or launch areas. Adequate signs will be posted to this effect and the rule will be rigorously applied by the race organisers and officials.

4. Points.

a) 400 Points for will be awarded to the winner in each formula/class ~~in a race where 3 or more boats cross the start.~~ with each subsequent finishers points reduced by 20, for example: -

i. First Place 400 Points

ii. Second Place 380 Points

iii. Third Place 360 Points

~~Points reduced by 10% for each subsequent position~~

b) All boats crossing the finishing line in a race will receive points subject the requirements below being met

c) Should a race be curtailed or stopped points will be awarded based on a boats position the last time they crossed the finishing line as long as the minimum race time as detailed below have been completed.

d) Points will be awarded to the boat / driver combination.

e) Points are not transferable into other classes or between boats. However, under exceptional circumstances a change of boat to one in the same class and transfer of points may be permitted by applying to the committee for a dispensation. Any replacement boat must carry the same number.

f) Points will only be awarded to Boats crossing the finishing line having completed 75% of their class winner's laps rounded down to the nearest whole lap.

g) Points will only be awarded upon 15 minutes of the scheduled race time (Normally 25minutes plus a lap) being completed as a single race. Should the scheduled race time be changed from the norm (above) this may be amended by the race committee.

h) The worst 6 races in a season will be deducted from the total points scored when calculating the National OCR Championship positions for each class. This will include did not finish (DNF) and did not start (DNS). Should the result be tied, the winner will be the boat with the most wins, seconds, or thirds etc. until there is a winner. Disqualifications cannot be dropped even though no points were awarded. This may be varied by the committee in exceptional circumstances e.g. insufficient races run.

i) Any driver / boat combination disqualified from a race because of a technical infringement WILL lose all points to date and those races may not be dropped as worst results for championship point's status.

- j) Any boat or crew returning to the pits after a race without all its required equipment may be disqualified.
- k) Any boat losing a cowling will be black flagged and should turn into the centre of the course when safe to do so and approach the boat flying the black flag to confirm the reason for the black flag. Losing a cowling and being black flagged will result in a did not finish (DNF)
- l) Spot checks will be carried out, unannounced, at races to verify that boats comply with the eligibility rules.

5. Alcohol and Drug Testing.

a) Alcohol

- i. Random testing for alcohol will take place at each event. Any competitor or official exceeding 5 micrograms of alcohol for every 100 millilitres of breath will be excluded from the event until they are within the allowed limit.
- ii. Retesting immediately before a race will be at the discretion of the race organisers / officials.
- iii. Where race organisers / officials have good reason to believe a competitor or race official may be over this limit they may ask for a breath test to be taken.
- iv. Any refusal to take a breath test without a medical reason will result in exclusion and **possible disqualification** from the rest of the event.
- v. Repeated failures of the breath test at different events will result in disciplinary action being taken and a written warning issued.

b) Drugs

- i. Random drug testing may be carried out at an event.
- ii. No competitor or official is to take any drug currently banned by the World Anti-Doping Agency (WADA)
- iii. Where race organisers / officials have good reason to believe a competitor or race official may be under the influence of drugs then they may ask for a test to be taken.
- iv. Should you believe that any prescribed or over the counter drug which you are taking is banned under WADA then you are to provide details to the club secretary admin@ocrda.com (in confidence) so that an exemption can be made if appropriate.
- v. Failure of a drug test at an event may result in a validated test being carried out the cost of which will be borne by the competitor if failed or OCRDA if passed.
- vi. Independent validated drug testing may be carried out at any event at the discretion of OCRDA committee, **UK National Powerboating Body (BPBA) or the UIM.**
- vii. Any refusal to take a drug test without a medical reason will result in exclusion from the rest of the event.

6. Valid Starters

A valid starter is defined as an entry accepted by the Organisers and having satisfactorily completed scrutineering, attended all required briefings and then crossed the start line as described in the racing instructions at the prescribed time, under the starting arrangements specified by the race programme or at drivers' briefing.

7. **Flags**

The following describes the flags used in a race (see race start procedure for start flags), their meaning and what action to take.

a) Blue “Race Official” Flag – This flag will be flown by signed on Safety and Marshall boats.

b) Yellow Flag – Warning

Unless flown in the muster from the start boat this is a warning flag carried by safety and marshal boats. It is used to advise race boats that there is an incident in the vicinity. At least one of the crew should acknowledge a yellow flag by raising their arm, do not overtake until clear and proceed with caution.

c) RED Flag – Race Stopped

Carried by safety and marshal boats the red flag immediately stops the race.

i. If the RED flag is deployed by the start boat during the start procedure all boats should come off the plane **when safe to do so** and return **safely** to muster to await further instructions.

ii. If the RED flag is deployed during a race all boats should come off the plane **when safe to do so** and return safely to the muster area **or as directed by a safety or marshal boat**.

iii. Any boat failing to come off the plane after passing 2 RED Flags will be penalised.

d) Black Flag – Boat Disqualified or Stopped from Racing

Carried by the start or finish boat (may be the same) and is used sometimes with a white board showing a boat number or pointed at a boat to instruct them to cease racing immediately and contact a safety boat for further instructions as they may be a danger to themselves and / or others.

e) Green Flag – Last Lap

Carried by the finish boat this is shown to the lead boat and all subsequent boats (irrespective of their position in the race) to indicate that they have commenced the last lap of the race.

f) Chequered Flag – Finish Flag

Shown from the finish boat to the lead boat and all subsequent boats one lap after the green last lap flag to indicate the race has finished. On receiving the chequered flag, it should be acknowledged, slow down when it is safe to do so and follow the race finished instructions as described at the Race briefing.

g) Chequered Flag NOT preceded by a Green Last Lap flag – Race Curtailed

Shown from the finish boat to the lead boat and all subsequent boats to indicate the race has been curtailed. On receiving this flag, it should be acknowledged, slow down when it is safe to do so and follow the race finished instructions as described at the Race briefing.

NOTE: Slower boats may be overtaken by the race leader on the last lap and may not receive a Last Lap Flag.

h) Orange Flag – Race Boat Retirement.

i. If flag is just held aloft then race boat has retired.

ii. If an orange flag is actively waved, then that race boat is in need of urgent assistance.

iii. Once an orange flag has been raised that race boat has retired and must not under any circumstances re-join the race.

iv. The Orange flag must continue to be shown by the retired boat until either the race has finished, or they are in the recovery area.

8. Posting of Results

- a) Where possible provisional results will be posted in or outside of Race Control within an hour of the last race of the day.
- b) The RCO or Race Manager will sign the provisional results and state the time of the posting.
- c) The RCO or Race Manager will be present for one hour from the time of posting the results to receive any protests.
- d) Provisional results will become official one hour after posting provided no protests have been received.
- e) It is the competitor's responsibility to monitor the posting of the provisional results.
- f) Only protests submitted in writing within an hour of the posting of results will be considered. **Protests after that time will only ~~not~~ be allowed if the crew of a protesting boat are incapacitated.**

9. Penalties & Warnings

- a) Time penalties for failure to run within the rules will be as detailed in the generic **and / or event specific** race instructions.
- b) Where the race officials feel a penalty does not reflect the actions of a competitor or that any advantage gained is more than the penalty detailed in Race Instructions then additional penalties will be applied. This could include additional time penalties or disqualification.
- c) Obvious deviations to the rules resulting in a **penalty or disqualification** being applied would include but not be limited to the following: -
 - i. Missing a mark(s) of the course.
 - ii. Failing to keep a safe distance at the start as detailed in the rules
 - iii. Jumping the start
 - iv. Dangerous, reckless and unsafe driving.
 - v. Failing to acknowledge red and yellow warning flags
- d) Bad behaviour by competitors at any time during the event will be discussed with race officials and if necessary, a written warning given detailing the reasons, the discussions, what is expected and what will happen should there be any repetition (**See Also OCRDA constitution document**).

10. Protests

All protests must be submitted on the appropriate form (available from race control) within one hour of provisional results being posted. There are 2 types of protest as follows: -

a) **Full Protest** –

- i. This must be submitted to the race secretary within the above timescale along with a protest fee of £100 cash. The RCO or Race Manager will then consider the protest, interview the parties involved and any witnesses, look at any supporting evidence and make their decision known along with any subsequent actions in writing to the protestor. Should the protest be upheld and there is no counter protest, (a counter protest fee of £100 cash is required) within 1 hour of this decision, the original protest fee will be returned and the matter closed.
- ii. The first protest will always be considered on the same day only with the evidence available at the time.
- iii. If the protest is not upheld or there is an appeal or counter protest this will be considered **by a different ~~an independent~~ Protest Panel** within 28 days and their decision will be final.

b) Reduced Protest

- i. This must be submitted to the race secretary within the above timescale. The RCO or Race Manager will then consider the protest, interview the parties involved and any witnesses, look at any supporting evidence and make their decision known along with any subsequent actions in writing to the protestor.
- ii. The decision of the RCO or Race Manager is final and cannot be appealed.

Section C – Launching & Start Procedures

1. Launching

- a) Boats must be ready to launch as indicated in **Race Instructions and confirmed at** the Race Briefing and under the instructions of the Launch Marshall. Failure to be ready for launching on time may result in you not being able to race or to be a late starter **meaning a boat will have to join the race once authorised and after the start run has commenced.**
- b) It is the responsibility of the boats crew / team to ensure the safety and security of their boat at all times and especially during launching and recovery when they should be present to assist and accompany the launch / recovery of their boat. OCRDA does not accept responsibility for any damage or loss incurred at an event no matter how caused.

2. Transit to and waiting in the Muster Area

- a) Boats must proceed to the muster area as detailed in race instructions and in an orderly fashion having due regard for harbour speed limits and other water users.
- b) When in the muster area boat must be off the plane bow down and no wake keeping a careful lookout for other boats.

3. Start Procedure – For Jet Ski Start Procedure please see Appendix 4.

- a) The start procedure will be fully explained in the race briefing including a description of the start boat and will be either a 'Rolling start' or an 'Off the Plane Rolling Start' In exceptional circumstances a foul weather start may be deployed (see below).
- b) The start chute, between the muster area and the first turning mark must be straight and of adequate length for the number of starters and be kept clear.
- c) **Rolling Start**
 - i. Once the course is clear, the start boat will raise and continue to display a yellow flag, this will indicate the commencement of the start procedure, during which time all boats should line up in an orderly fashion in preparation for the start.
 - ii. The start boat will then travel from its start position across the start chute and then return to its start position and commence the start run by turning away from the fleet picking up speed and on the plane towards the first turn mark.
 - iii. At this time race boats should follow and be in line abreast and / or as detailed in race instructions / briefing and follow the start boat at a distance of at least 30 meters and spaced at least 3 meters apart from other race boats, picking up speed in line with the start boat.
 - iv. When the starter is satisfied that all boats are in an acceptable racing line and proceeding at a suitable speed, the green flag will be raised and the yellow flag lowered simultaneously - **The raising of the green flag determines the start of the race.**
 - v. During the start run to the first mark competitors must have due regard of the overtaking rules and distances to be left between boats (see iii above).

- vi. If at any time during the start procedure (prior to the green flag being raised) a red flag is raised, the start has been aborted and all boats must return off plane to the muster area for a restart or follow specific instructions of the start or other officials / safety boat.
- vii. A boat that is in the muster area but is unable to start the race for any reason must not interfere with the start.
- viii. Late starters are only permitted at the discretion of the Safety Officer / Race Manager. Alternative instructions for late starters may also be given in the Race Instructions or at the drivers' briefing.
- ix. Should any boat decide not to proceed with the race they must follow the retirement procedure and deploy the orange flag.
- x. The start is one of the most dangerous times in a race and as always safety is paramount and takes precedence over racing. Drivers should do nothing to endanger their crew, those in other race boats, or official and spectator boats.**

d) Off the Plane Rolling Start

- i. Once the course is clear, the start boat will raise and continue to display a yellow flag, this will indicate the commencement of the start procedure, during which time all boats should line up in an orderly fashion in preparation for the start.
- ii. The start boat will then travel from its start position across the start chute and then return to its start position and commence the start run by turning away from the fleet picking up speed off the plane towards the first turn mark.
- iii. At this time race boats should follow and be in line abreast and / or as detailed in race instructions and the briefing the start boat at a distance of at least 30 meters and spaced at least 3 meters apart from other race boats, off the plane and at a speed in line with that of the start boat.
- iv. When the starter is satisfied that all boats are in an acceptable racing line and proceeding at a suitable speed, the green flag is raised and the yellow flag lowered simultaneously - **The raising of the green flag determines the start of the race and boats may increase speed on the plane.**
- v. During the start run to the first mark competitors must have due regard of the overtaking rules and distances to be left between boats (see iii above).
- vi. If at any time during the start procedure (prior to the green flag being raised) a red flag is raised, the start has been aborted and all boats must return off plane to the muster area for a restart or follow specific instructions of the start or other officials / safety boat.
- vii. A boat that is in the muster area but is unable to start the race for any reason must not interfere with the start.
- viii. Late starters are only permitted at the discretion of the SCO / RM. Alternative instructions for late starters may be given in the Race Instructions or at the drivers briefing.
- ix. Should any boat decide not to proceed with the race they must follow the retirement procedure and deploy the orange flag.
- x. The start is one of the most dangerous times in a race and as always safety is paramount and takes precedence over racing. Drivers should do nothing to endanger their crew, those in other race boats, or official and spectator boats.**

e) Foul Weather Start

Should sea conditions dictate ~~in the muster area be such that boats ship water when in the muster in an area in an area while off the plane~~, the start procedure will be modified as follows: -

- i. The start boat will lead all race boats to the muster area flying a yellow flag.
- ii. The start boat will head towards the first mark slowly on the plane to allow race boats to get safely in line on the plane.
- iii. Race boats will follow the start boat at the 30 metres minimum safety distance until the raising of the green flag.
- iv. Once satisfied that boats are reasonably in line the start boat will raise the green flag and the race will commence.

f) Late Starters

Late starters can only join the race after confirmation that they are allowed to do so from race control via VHF radio or a safety boat.

Section D – Racing Rules

1. General

- a) It is the duty / responsibility of each crew member to ensure that their boat is driven in a manner that does not compromise the safety of themselves, any other competitor or any spectator. Different boats and different classes of boat handle and respond in different ways and different weather and sea conditions affect the way boats handle.
- b) The amount of sea room required, and time needed to make a manoeuvre or avoid a collision will vary from boat to boat and race to race. This must be considered when following these rules.
- c) **Both crew must always be sat in one of the fitted seats whilst on the plane.**
- d) Whilst racing or participating in official practice sessions, boats are still bound by the International Rules for the Prevention of Collision at Sea in regard to other water users which are not part of the event.
- e) It is the responsibility of each crew member to ensure they are fully aware of the consequences of their actions and to anticipate the actions of other boats in their immediate vicinity. All crew members must take any action necessary to avoid a collision. A constant lookout must be maintained and crews are reminded of the importance of good and efficient communication between them at all times.
- f) Any boat involved in a collision WILL be disqualified. Where a competitor believes that contact was of no fault of theirs, they may continue to race if it is safe to do so and lodge a reduced protest procedure once the race is over and within an hour of results being posted.
- g) Flag Signals – Boats must obey all flag signals given by officials during testing, practice and racing. Failure to comply with flag signals may result in a penalty or disqualification.
- h) No outside assistance (including refuelling) is allowed during a race. Any boat receiving unauthorised outside assistance will be disqualified.

2. Wet Driver / Crew (Excludes Jet Ski's)

- a) In the event of either crew of a boat being ejected into the water all racing will stop regardless of whether the red flag is being flown.
- b) Irrespective of a red flag being flown if any boat comes across crew in the water, they must immediately stop to offer assistance, warn other boats to keep clear and try and alert one of the safety team if not already in attendance.

3. Accident Aid

- a) It is mandatory for the first boat to stop and give support at an accident – however, crew must only give active assistance if requested or there is none or insufficient help at the scene.
- b) The first boat which stops to render assistance as detailed above will be awarded points related to the position they held the last time they crossed the start finish line prior to stopping to give support at an accident. No other finishers will have their points or positions affected by this action. However, should the boat that rendered assistance restart the race and improve its position from when it stopped, it will keep its better position and points. To qualify the boat giving assistance must take the chequer flag.

4. YELLOW FLAG - Incident Procedure

- a) In the event of a hazard or incident on the course, the yellow flag procedure will be used to control the fleet.
- b) There is NO OVERTAKING in the vicinity of the yellow flags.
- c) When it is deemed that the course is clear, yellow flags will be removed.
- d) It is all crew member's responsibility to monitor and acknowledge all flag signals whilst deployed and act accordingly, especially in the vicinity of any incident.
- e) Any crew not following these instructions may be liable for disqualification.

5. RED Flag – Stopping a Race

- a) In the event of crew being in the water the race will be stopped irrespective of whether a red flag is being flown **(Excludes Jet Ski's)**.
- b) In the event of force majeure, the race will be stopped by waving the RED flag from all official safety and marshal boats.
- c) On seeing RED flags, boats are to stop racing immediately, come off the plane and return safely to the muster area **or as detailed in race instructions / briefing**.
- d) In the event of the race being stopped using the Red Flag procedure, the finishing positions will be taken as recorded the last time a boat crossed the start finish line and if applicable points awarded based on time elapsed as detailed in Section C.
- e) Any boat deemed to be the cause or a contributory factor in the race being aborted will be disqualified.

6. Overtaking

- a) Any overtaking boat must give way to the overtaken boat.
- b) A boat being overtaken must not deliberately alter its course in any way that would hinder the overtaking boat
- c) An overtaking boat must **give way to and not cause the overtaken boat to change course or take evasive action and** in all circumstances be prepared to alter its course to avoid a collision.
- d) **During Multi-Class races, boats on a longer course may only pass on the outside of the boats those on the shorter course unless instructed otherwise at the pre-race briefing i.e. rounding a chicane.**
- e) Extra caution is advisable when overtaking canopied boats that may have limited all-round visibility, especially to the rear.
- f) If a boat in consequence of its neglect of any of these rules compels another to foul, it will be disqualified.

- g) Definition of fouling - if any boat by its action causes another boat to have a collision or causes another boat to take action to avoid a collision which may or may not result in that boat infringing another rule. (e.g. missing or hitting a mark of the course), they will be penalised.
- h) Any/all boats involved in a collision will be disqualified.

7. Multi Class Racing

- a) Multi class racing can incorporate two or more courses.
- b) During Multi-Class races, boats on the longer course may only pass outside of the boats on the shorter course, except on a chicane where the responsibility is on the overtaking boat. This will be clearly described at drivers briefing.
- c) If canopied boats are racing in a mixed class event, competitors are to be particularly careful when overtaking as these boats have limited all-around visibility, especially to the rear.

8. Turn Marks – Rounding, Fouling and Missing

- a) All marks will be laid in the approximate positions referred to in the race instructions.
- b) It is the competitor's responsibility to drive close enough to the course marks to ensure that they have been seen to pass them correctly.
- ~~c) Where 2 or more boats approach a turn mark, they should give way to the boat on their inside and ensure enough room is left for them to take the mark safely. Any boat on the inside must not deliberately alter course or take the mark wide where it might force the boats on the outside to take avoiding action. See overtaking rules~~
- d) The Event Race Instructions will specify the colour and shape of the course marks.
- e) Should a mark go missing the race will be stopped but until that happens the Boat must pass through the approximate geographical position referred to in race instructions and not seek to gain an advantage.
- f) If a boat damages a turn mark a penalty may be applied by the race officials and any damage / loss charged to the competitor.
- g) Should a mark be missed it is not to be retaken and the boat must continue around the designated course.
- h) Any boat missing a mark will receive a penalty as detailed in these rules or Race Instructions, however, any penalty may be increased should it be deemed that a boat has gained an advantage over and beyond the penalty given.
- i) Any boat considered to be driving dangerously **by missing more than one mark may** receive further penalties or be disqualified.

9. Finishing a Race

- a) When the leading boat has completed the time or laps as detailed in race instructions, they and all boats following will receive the Green Last Lap Flag at the start / Finish line.
- b) When the leading boat completes the last lap and crosses the finishing line, the chequered flag will be waved indicating they are the winner and that the race is finishing.
- c) The chequered flag will also be given to all subsequent boats that cross the finish line.
- d) After crossing the finishing line boats should continue for a short distance before slowing down and turning into the centre of the course or as described in race instructions conforming with the International Regulations for Preventing Collisions at Sea. They should then await further instructions from a Marshal / Safety Boat before being escorted back to the wet pits for recovery

- e) Boats shall not begin a new lap if they cross the finish line after the leading boat has taken the chequered flag, should any boat fail to stop racing a penalty will be applied.
- f) All boats crossing the finishing line after the winning boat will be classified as having finished the race and timed for completing a race when her bow crosses the finishing line.
- g) Time Limit - All boats have a maximum of 15 minutes from the time the winning boat crosses the finish line to complete their final lap otherwise they will be classed as a non-finisher.
- h) Boats will be ranked according to the number of laps completed and then the time it has taken to complete those laps.

10. Race Curtailment.

- a) A race may be curtailed at any time for a number of reasons but especially on the grounds of safety and curtailment will indicate the finish of the race.
- b) For curtailment of a race the Chequer flag (without the last Lap flag) will be flown by the finish Boat at the Start / Finish Line starting with the lead boat.
- c) All boats will then follow the finish procedure as detailed above.

11. Retirement Procedure

- a) On retiring from a race, boats must hoist and display an orange flag when practical to do so and continue to fly it until the boat is back in the wet pits.
- b) The crew should attempt to contact a safety / marshall boat or Race Control by radio and inform them of the boat's retirement and the reasons.

12. Injured Crew

- a) In the event of any competitor being injured they should, if possible, seek immediate medical assistance from the medical officer at the event and / or notify race control or a safety boat.
- b) Should the injury be such that the Medical Officer considers it is unsafe to continue racing he will advise Race Control and the competitor's licence will be withdrawn preventing him from racing until notification is received in writing from their doctor or the hospital that they are fit to do so.
- c) Any Injuries incurred whilst at an event should be declared as soon as practical to race control, which will be recorded and kept for future reference if needed.



Section E – Jet Ski Appendices

Appendix 1 – Modifications permitted in 300 hp and 200 hp stock

1. Handling

- a) Ride Plate - Pump cover plate may be modified or aftermarket. An extension may be added to the rear of the pump cover plate but shall not exceed the width of the original equipment plate. Modified and aftermarket plates must not extend more than 177.80mm (7.00 in.). The sides of the extension must be connected to the radiused portion of the pump plate so as not to create a hazard. Fins, rudders, skegs and other appendages that may create a hazard will not be allowed.
- b) All watercraft may be equipped with a maximum of two sponsons. Stock sponsons may be modified or aftermarket. Sponsons shall not exceed 91.45cm (36.00in.). Sponsons shall not protrude from the side of the hull by more than 100.00mm (3.94 in.) when measured in a level horizontal plane. The vertical channel created by the underside of the sponson shall not exceed 63.5mm (2.50in.). No part of the sponson shall extend downward below the point at which the side of the hull intersects the bottom surface of the hull by more than 38.00mm (1.50 in.). Aftermarket or modified sponsons must exceed 6mm (0.24 in.) in thickness. All leading edges must be radiused so as not to create a hazard. Sponsons may not be attached to the planeing surfaces of the hull. Fins, rudders, skegs and other appendages that may create a hazard will not be allowed.
- c) Intake grate may be modified or aftermarket. Intake grate is required and must be the full-length type with at least one bar running parallel to the drive shaft. Grates may not extend more than 12.00mm (0.47 in.) below the flat plane of the pump intake area. All leading edges must be radiused so as not to create a hazard.
- d) Steering system may be after market. Handlebar, throttle, throttle cable, and grips may be modified or aftermarket. Handlebar cover may be modified or removed. Aftermarket switches and switch housings may be used. Steering shaft, steering shaft holder and handlebar holder may be aftermarket. The handlebar must be padded at the mounting bracket or, if it has a crossbar, the crossbar must be padded. Aftermarket steering cables are allowed.
- e) Seat structure must remain stock. Seat covers are permitted.

2. Air and Fuel Delivery

- a) Air and fuel delivery must remain stock as furnished by the OEM.
- b) Craft will be allowed to utilize an aftermarket catch-can. Excess oil/fuel exiting the catch-can must be caught and not spill into the engine compartment.
- c) An aftermarket blow-off valve (BOV) may be used.

3. Driveline / Pump Area


- a) Driveline, pump stator, nozzles must remain stock as furnished by the OEM.
- b) Impeller must remain stock as supplied by the manufacturer.
- c) Replacement wear rings that are within OEM internal diameter specifications may be used. Silicone adhesive sealant may be used in addition to original equipment seal to seal pump inlet.
- d) Yamaha models - Sound suppression plate and bracket (around pump area) may be removed. Exhaust flap must remain in position.

4. Ignition and Electronics

All electronics must remain stock as furnished by the OEM.

Appendix 2 – Jet Ski Numbers

1. Numbers must be on a contrasting background. For example, if your ski is white, your numbers must be black or white numbers must have a black background.
2. All numbers must be forward of handlebars, to make it easier for race officials and lap scorers to see.
3. Required size, position and design are as the examples below.
4. If your number is not read correctly, because it does not meet the above requirements your lap may not be counted.



For Size & Spacing see section A.9

Appendix 3 – Jet Ski Helmets

Helmet: A properly fitting, full coverage helmet with double D ring fastener and chin and mouth protection (motocross type) that meets current international recognized standards must be worn at all times while on the water and that offers a level of safety and protection equivalent to the following examples.

- a) Comply Snell M2010 or DOT FMVSS 128 Safety standards for motorcycle use
- b) Comply British Standard BS 6658:1985 - Kitemark
- c) Comply with UNECE Regulation 22.05
- d) Comply with any standard accepted by a member of the European Economic Area which offers a level of safety and protection equivalent to BS 6658:1985
- e) The helmets must be in excellent condition and devoid of any damage that could impair the structure and effectiveness of the helmet.
- f) The helmet must have a minimum of 50% coverage of hi-visibility/bright colour – no black or dark coloured helmets allowed.
- g) Helmets will be approved by the scrutineer at pre-race technical inspection

Appendix 4 – Jet Ski Starting Procedure.

1. ENDURO – J1, J2, J3

Classes will race together unless stated otherwise in the Race Instructions or at Riders Briefing. If numbers dictate, a staggered start may be used. Start system will be explained at Riders Briefing.

2. Starting positions

Will be determined by the following method: -

- Race 1 - Starting positions will be decided by random pick when registering.
- Race 2 - Starting positions will be decided by finishing position of Race 1.
- Race 3 - Starting positions will be decided by finishing position of Race 2
- Race 4 - Starting positions will be decided by finishing position of Race 3

3. Notes

- Under 18 or new riders, will be positioned on the outside of the class line.
- J1, J2 & J3 classes will line up for the start in this order.
- Riders must observe a distance of 2m/6ft between craft.

